

BRUHAT BANGALORE MAHANAGARA PALIKE
YELAHANKA ZONE

Name Of Work :- Detailed Estimate for Supplying and installation of street light panel boards in Yelahanka zone

Budget Head

Division No.....

Estimate No.

For Rs.=

500000.00

Sl. No.	Description of Work	Qty.	Rate Rs. Ps.	Unit	Amount
1	Supplying of 1.1KV grade Aerial Bunched Cable Stranded & Compacted Aluminum Phase Conductor, and Stranded Messenger Conductor with all aluminum Alloy, Phase Conductor is insulated with XLPE Compound, insulated Messenger with specified IS-14255:1995 & confirming to GTP of GROUP-A.2 X 25 + 1 X 25 SQ.MM KPWD ELE SR 2014-15	150	143.00	Per Mtr	21450.00
2	Stringing of 1.1kv LT Aerial Bunched Cable, BESCOM SR	150	10.30	Per Mtr	1545.00
3	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Icu = Ics) THREE POLE 100Amps 25kA.26/5.14.1	6	4530.00	Each	27180.00
4	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A.4 core 16 sqmm40/6.4.4	200	150.00	Mtrs	30000.00
5	Labour charges for laying of 1.1 KV class UG cable when supplied agency in existing trench GI pipe / stoneware pipe / on wall / on pole as required. 1. In existing trench/duct. 6 sqmm to 16 sqmm	200	30.00	Mtrs	6000.00
6	Digging of trench of 0.6 m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc.,complete.41/6.6.1	150	76.00	Mtrs	11400.00
7	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 7 tanks treatment with powder coated paint and finally finished with approved colour etc., complete.16SWG KPWD ELE SR Page-30/5.42.2	180000	0.35	sq.cms	63000.00
8	Wiring for lighting/power circuit using one of PVC insulated 1100v grade, multis and Copper conductor single core cable in open or consealed system of wiring.I Group A Materials.6 sqmm 6/2.3.3	175	70.00	Mtrs	12250.00

9	Thiristor based single/ Three phase smart street light control and monitoring system Remotely control and and monitorable smart street light system by using web or mobile application .smart control system has hardware ruggedness over field issues like line cross, line short, lighting and any other irregularities in voltage. It has some features like 1.Remote lighting management.2.Precise lighting turnoff.3.Load ballancing.4.Load power regulation.5.Status tracking. It works on the basis of some of these features 1) Main Control Unit (Mother board) : Handles controlling , data handling and other communication process. 2) Communication unit: GSM/GPRS quad bandwith RS232 interface wireless communication unit 3) Gate Driver Unit: Firing angle controllable board for driving the thyristor 4) Switching Thyristor: SCR 110 AMPS dual thyristor modules for switching 5)Embedded Firmware: Firmware to control , handle , process the data and communicate it wirelessly.6) Metal Enclosure : IP66 weather prof metal enclosure. 7) transformers: Customized step down transformers for various purposes.8) Wiring and other device assembly components.	6	51500.00	No	309000.00
10	GST 12% ON item No 3 to 8				17979.60
11	Misleniuos				195.40
	Total Rs				500000.00

CERTIFICATE

1. The Place was inspected and work is essential
2. The Provision made in the estimate is adequate and are necessary.
3. The Work comes in the BBMP limit and is legitimate charges on the Corporation Funds.
4. The rates in the Estimate is based on AR/2019-20 / , BESCOM SR approved rates

Asst. Engineer (Elec)

Asst. Exe. Engineer (Elec)
Sub-Division No.

Bruhat Bangalore Mahanagara Palike

EXECUTIVE ENGINEER (ELEC)
YELAHANKA DIVISION
BRUHAT BANGALORE MAHANAGARA PALIKE

Administrative Sanction for Rs. 500000.00
Rupees FIVE LAKH ONLY

is accorded P 3254 MAINTENANCE
OF COMMUNITY HALL (ELECT-
RICAL 32 COMMUNITY HALLS)

Registered as El. 32/2019-20 Subject
to conditions of

No. BBMP/EE/EIC/42/AS/32/19-20
Dt 18-12-2019

Executive Engineer

TECHNICALLY SANCTIONED FOR Rs. 500000.00
Rupees FIVE LAKH ONLY

Under P 3254 MAINTENANCE
OF COMMUNITY HALL (ELECTRICAL)

Registered as 19/2019-20 9 9
Subject to BBMP/EE/EIC/42/AS/32/19-20
enclosed memo dt 18-12-2019
BBMP/EE/EIC/42/TS/19/2019,20
Dated 18-12-2019 Rs. 500000.00

Executive Engineer